

- 14 **ENSURE** that the timber used as sole plates is long, wide and thick enough to take the weight of the load.
- 15 **ENSURE** that the support prop is of the correct length to carry out the work and **DO NOT** use timber to make up the short fall in length.
- 16 Inspection of the support props is to be carried out by a competent person on a weekly basis.
- 17 **DO NOT** adjust or remove any support prop unless it is safe to do so.
- 18 **DO NOT** attach any electrical or lighting cables to the support props.
- 19 **ENSURE** that if support props are left unattended the area is made safe against unauthorised persons.
- 20 **DO NOT** attempt repairs. Contact the Hire Company