

- 13 **DO NOT** pass items that are of a larger dimension than the diameter of the chute. Cut large lengths of timber before tipping them down the chute.
- 14 **ENSURE** that the chute is regularly checked for blockages.
- 15 If a blockage occurs there should be no further use of the chute until the blockage has been cleared.
- 16 **DO NOT** over fill the skip, as this is the most frequent cause of a blockage.
- 17 **ENSURE** that all blockages are cleared, all securing points are free and the rubbish skip is removed before lowering the chute.
- 18 A competent person **MUST** supervise the clearing of all blockages to provide a safe system of work.
- 19 **DO NOT** tip flammable liquids or hot materials down the chute that could cause damage or a fire.
- 20 Dismantle the chute by reversing the erection procedure.
- 21 **DO NOT** attempt repairs. Contact the Hire Company.