

- 8 **ENSURE** that you understand all the controls and how the equipment operates before you start.
- 9 **ENSURE** that the fluid in the reservoir is the correct type for the components being tested.
- 10 **ONLY** use hose that have been supplied by the Hirer.
- 11 **ENSURE** before disconnecting, adjusting or topping up fluid levels that the pressure has been dissipated.
- 12 **ENSURE** that all pipes, hoses, blanking plugs and components are tight and safe before testing commences.
- 13 **ENSURE** that the pressure has been released and isolated before leaving unattended.
- 14 **DO NOT** exceed the stated pressures of either the installation or the test equipment.
- 15 **ENSURE** that all flexible hoses are examined prior to pressure testing. Safety restraints should be attached to prevent flexible hoses flailing about during pressure testing.
- 16 **ENSURE** that all pressure gauges used for pressure testing have been calibrated with a known gauge and records of comparison kept. Any gauge used during the test should have a current certificate of calibration attached.
- 17 Temperature gauges may be required to check the testing medium.
- 18 **DO NOT** wedge any switch or lever in the open or closed position as it may cancel safety device operations.
- 19 **DO NOT** attempt repairs. Contact the Hire Company